

QOREVA™ DOCUMENT INTELLIGENCE VALIDATION

Clean Excavation Work Package — Test Document

Purpose: This synthetic document is designed to test whether Qoreva distinguishes resolved planning information from genuine gaps. It is not a work authorization and must not be used for field execution.

Project	Qoreva Validation Project
Task	Install 18-inch storm sewer in open excavation
Location	Building D — East Utility Corridor
Planned excavation	Approx. 7 ft deep × 5 ft wide × 80 ft long
Crew	6 workers — day shift
Planned date	October 12, 2026
Competent Person	Jordan Ellis — Excavation Competent Person
Excavation Supervisor	Morgan Reed

1. Scope and Work Sequence

The crew will establish the work zone, verify existing underground utilities, excavate the storm sewer trench, install bedding and 18-inch storm pipe, complete connection work, backfill in controlled lifts, compact, and restore the work area. Mechanical excavation may begin only after the utility-verification steps below are completed.

2. Underground Utility Verification

Miss Dig ticket 2026-104812 is active for the planned work area. Available project utility drawings were reviewed during preplanning. GPRS completed supplemental private-utility locating on October 9, 2026. Two existing utilities cross or approach the planned excavation: an electrical duct bank and a 2-inch natural-gas service. Both have been positively identified by vacuum excavation and exposed at the crossing/closest-approach locations. Daylight points are marked in the field and shown on the excavation sketch. No unresolved utility shown on the reviewed records remains within the planned mechanical excavation limits. Before mechanical excavation begins each shift, Jordan Ellis will verify the locate markings and daylight points remain visible and consistent with the excavation limits. If markings are lost, field conditions conflict with the records, an unidentified line is encountered, or the excavation extends beyond the verified area, mechanical excavation will stop until the condition is resolved.

3. Excavation Protective System

The planned excavation is approximately 7 ft deep. Jordan Ellis classified the soil during preplanning as Type C for planning purposes. A manufacturer-rated trench shield suitable for the planned depth and soil condition will be used whenever employees enter the excavation. The shield will be installed and used in accordance with manufacturer requirements. Spoils and equipment will be kept at least 2 ft from the excavation edge. The Competent Person will inspect the excavation, protective system, adjacent area, and changing conditions before each shift and as conditions warrant.

4. Access and Egress

A secured extension ladder will provide access and egress. The ladder will extend at least 3 ft above the landing and will be positioned so employees working in the trench do not travel more than 25 ft laterally to reach an exit. The ladder location will be adjusted as the work progresses so the maximum travel distance is maintained.

5. Water and Weather Controls

The excavation area will be inspected for water accumulation before entry and throughout the shift. A portable pump is available if incidental water enters the excavation. Employees will not enter an excavation with hazardous water accumulation. Work will stop and the excavation will be re-evaluated following heavy rain, significant water intrusion, or other conditions that could affect soil or protective-system stability.

6. Atmospheric Hazard Evaluation

No known atmospheric hazard source is identified for the planned open excavation. The Competent Person will reassess conditions before entry and whenever conditions change. Atmospheric testing will be performed before entry if there is reason to suspect oxygen deficiency or a hazardous atmosphere, including evidence of a leak, unusual odor, nearby hazardous process release, contaminated soil, or other changed condition. If testing indicates a hazardous atmosphere, entry will stop until appropriate controls and authorization are established.

7. Mobile Equipment and Excavation Edge

Equipment operating near the excavation will maintain separation from the edge appropriate to soil and site conditions. A designated spotter will be used when the operator's view of the edge, workers, utilities, or travel path is restricted. Workers will remain outside equipment swing and backing zones unless communication and positioning controls are established.

8. Required PPE

Minimum PPE: hard hat, safety glasses with side shields, high-visibility vest or garment, work boots, and task-appropriate gloves. Additional PPE will be selected if conditions or specific tasks require it.

9. Stop-Work Triggers

Stop work immediately for an unidentified or conflicting utility; damaged or missing locate marks; unexpected soil change or excavation instability; water accumulation creating a hazard; protective-system damage or improper positioning; hazardous-atmosphere indication; unauthorized entry; loss of required access/egress; or any condition the Competent Person determines is unsafe. Work resumes only after the condition is evaluated and appropriate controls are restored.

10. Emergency Response

For a utility strike, collapse, hazardous atmosphere, serious injury, or other emergency, workers will stop work, keep personnel out of the affected area, and contact site emergency services using the project emergency communication process. Workers will not enter an unstable excavation or hazardous atmosphere to attempt rescue unless specifically trained, equipped, and authorized for that response. The supervisor will preserve the area as appropriate and initiate required incident notifications.

11. Pre-Work Verification and Authorization

Before mechanical excavation begins, the Excavation Supervisor and Competent Person will verify: active locate ticket; required utilities positively identified; daylight points and field markings visible; excavation limits confirmed; protective system available and suitable; access/egress available; equipment and spotter arrangements established; weather/water conditions acceptable; crew briefed on the work sequence and stop-work triggers; and required permits/authorizations complete.

12. Verification Record

Verification Item	Status	Verified By
Active utility locate ticket reviewed	Complete	Jordan Ellis
Electrical duct bank positively identified/daylighted	Complete	Jordan Ellis
Natural-gas service positively identified/daylighted	Complete	Jordan Ellis
Excavation limits and daylight points marked	Complete	Morgan Reed
Trench shield available and inspected	Complete	Jordan Ellis
Access/egress ladder available	Complete	Morgan Reed
Crew pre-task briefing	Complete	Morgan Reed

13. Approval / Sign-Off

Excavation Competent Person: Jordan Ellis **Status:** Reviewed / Ready for planned work

Excavation Supervisor: Morgan Reed **Status:** Reviewed / Ready for planned work

Validation note: This is a synthetic test document. Qoreva should not treat the document as an actual authorization to perform excavation. The document intentionally provides specific answers for utility verification, responsible persons, protective system, access/egress, atmospheric evaluation, stop-work criteria, and pre-work verification so false-positive behavior can be evaluated.