

QOREVA™ DOCUMENT INTELLIGENCE VALIDATION

Elevated Work / Fall Protection Plan - Synthetic Test Document

TEST ONLY - NOT AUTHORIZATION FOR FIELD EXECUTION. This synthetic plan contains a mixture of complete fall-protection controls and selected unresolved planning details. It is intended only to evaluate Qoreva Document Intelligence.

Project	Qoreva Validation Project
Task	Install overhead cable tray and supports
Location	Process Building - Level 2
Working height	Approximately 22 ft above lower level
Primary access	Mobile elevating work platform (MEWP)
Crew	4 workers - day shift
Competent Person	Jordan Ellis
Planned date	October 16, 2026

1. Scope and Work Sequence

The crew will establish the elevated-work area, inspect the MEWP, move materials to the work location, elevate two workers to install cable-tray supports and tray sections, make mechanical connections, lower the platform, and remove the controlled work area. Work will stop if conditions change or the planned access method cannot be maintained.

2. Access Equipment and Operator Controls

A boom-type MEWP will be used as the primary access method. Only trained and authorized operators may operate the MEWP. A pre-use inspection and function test will be completed before use. The MEWP will be positioned on a firm surface within the designated work area. Ground personnel will maintain communication with the operator and keep unauthorized personnel clear of the operating envelope.

3. Personal Fall Protection

Workers in the boom-lift platform will use a full-body harness and manufacturer-compatible connecting device attached only to the designated platform anchorage. Harnesses and connecting devices will be inspected before use. Workers will remain inside the platform and will not climb or stand on guardrails. The selected connecting system must be appropriate for the specific MEWP and manufacturer requirements.

4. Dropped-Object / Barricade Controls

The area below elevated work will be barricaded and controlled to prevent unauthorized entry. Tools and small components will be secured when there is a credible dropped-object exposure. Materials will be kept within the platform capacity and arranged so they do not create a falling-object hazard.

5. Weather and Environmental Conditions

Outdoor portions of the task will stop during lightning, severe weather, or wind conditions exceeding the MEWP manufacturer's operating limitations. The operator and Competent Person will reassess conditions if weather changes during the task.

6. Rescue and Emergency Planning

Ground personnel will be present while the MEWP is elevated and will be familiar with the ground-control lowering function. If the elevated operator becomes incapacitated and normal lowering is unavailable, the crew will contact the site's emergency response resources and follow the project emergency process. The work package does not include the project emergency contact number or a documented site-specific elevated rescue method beyond use of ground controls and site emergency response.

7. Nearby Electrical Exposure

The planned work area is near existing electrical distribution. The crew will maintain the required approach distance from exposed energized parts. If the planned MEWP position or cable-tray installation could encroach on the required clearance, work will stop until the electrical condition is evaluated and an approved control is established. The voltage of the nearby electrical system and the required approach distance are not documented in this package.

8. Anchorage / Connecting-System Selection

The MEWP platform contains a manufacturer-designated anchorage point. The exact harness/lanyard or self-retracting device to be used has not yet been assigned to the crew, and the equipment-specific compatibility check will be completed before work begins.

9. Stop-Work Triggers

Stop work for loss of stable MEWP setup, failed pre-use inspection, missing fall-protection equipment, damaged anchorage or connecting equipment, unauthorized entry into the controlled area, lightning or excessive wind, inability to maintain electrical clearance, loss of ground support, or any condition determined unsafe by the operator or Competent Person.

10. Pre-Work Verification

Verification Item	Status
MEWP operator training/authorization	Confirmed
MEWP pre-use inspection / function test	Required before use
Platform designated anchorage	Confirmed
Barricaded drop zone	Planned
Specific harness / connecting device assignment	Pending
Nearby electrical system voltage / required clearance	Not documented
Site-specific elevated rescue details / emergency contact	Not attached

11. Review / Sign-Off

Competent Person: Jordan Ellis - Reviewed for validation

MEWP Operator: Casey Morgan - Training/authorization confirmed

Electrical Qualified Person Review: _____ - Pending

Validation note: Qoreva should recognize documented controls such as trained MEWP operation, designated platform anchorage, barricading, equipment inspection, weather stop-work criteria, and ground-control awareness. It should scrutinize unresolved information without inventing project facts.